

SC160 Method IIIC Construction

(June 2000)
(Rev.1
Nov 2005)

(Reg. II-2/7.5.5.3)

In the case of ships built in accordance with Method IIIC, the detection system is only relevant to the accommodation block. Service spaces built away from the accommodation block need not be fitted with a fixed fire detection system.

Note: This UI SC 160 is to be uniformly implemented by IACS Members and Associates from 1 January 2001.

